

| Sl. No. | Item of work                                                                                      | Unit     | Quantity  | Rate in figures | Rate in words |
|---------|---------------------------------------------------------------------------------------------------|----------|-----------|-----------------|---------------|
|         |                                                                                                   |          |           | Rs. a. p.       | Rs. a. p.     |
| 11      | Teak wood glazed semi-circular ventilators...                                                     | S.ft.    | 25        |                 |               |
| 12      | Teak wood wrought and put up with wood oiling.                                                    | C.ft.    | 172.63    |                 |               |
| 13      | Roofing with first class Mangalore tiles on teak reapers with nails complete                      | Sqr.     | 27.82     |                 |               |
| 14      | Mangalore Ridge Tiles set in cement mortar.                                                       | R.ft.    | 107       |                 |               |
| 15      | Plastering with mortar inside                                                                     | Sqr.     | 80.42     |                 |               |
| 16      | Rough plastering outside marking with trowel with cement wash as shown in plan.                   | "        | 18.15     |                 |               |
| 17      | Chunam patties on rough plaster outside with white washing complete as per plan.                  | R.ft.    | 803       |                 |               |
| 18      | White washing two coats                                                                           | Sqr.     | 80.42     |                 |               |
| 19      | Pointing the basement with cement mortar.                                                         | "        | 7.94      |                 |               |
| 20      | Chocolate painting two coats                                                                      | "        | 5.45      |                 |               |
| 21      | Flooring with cuddapah slabs on 3" thick concrete bed with cement pointing.                       | "        | 13.57     |                 |               |
| 22      | Chunam borders over roof 6" thick                                                                 | R.ft.    | 89        |                 |               |
| 23      | Teak wood cave board with painting                                                                | "        | 318       |                 |               |
| 24      | Teak wood finials                                                                                 | Each     | 4         |                 |               |
| 25      | Teak wood pendants                                                                                | "        | 8         |                 |               |
| 26      | Providing teak wood gate topass ages of central rooms with iron works, painting complete.         | S.ft.    | 48        |                 |               |
| 27      | Providing teak wood gate to main entrance with zinc sheet covering iron works, painting complete. | "        | 66        |                 |               |
| 28      | Drilling holes in gate pillars                                                                    | Each     | 8         |                 |               |
| 29      | Cutting niches in bearing slabs to hold struts in front.                                          | "        | 10        |                 |               |
| 30      | Clearing site and levelling ground                                                                | Lump sum | in rupees |                 |               |

A. TANDONI RAO,  
Executive Engineer,

### SRI CHAMARAJENDRA WATER WORKS DIVISION.

#### Abstract Notification.

The attention of the public is invited to the notification, calling for tenders for conveying alum, pipes and other heavy materials from Bangalore City Station to Thippagondanahalli, published in Part VI, page 520 of the *Mysore Gazette*, dated 4th May 1933.

The last date fixed for receiving tenders is 22nd May 1933.

#### Notice of sale of scrap iron.

Sealed tenders are invited up 2 P.M. on 28th May 1933 for the purchase of iron scrap consisting of unserviceable mortar mills, corrugated iron buckets, mild steel bars, mortar pans, hammers, marmies, pickaxes, etc., released from works.

2. The rate per ton at which the material can be purchased at site of works or stores should be clearly noted and no claim for dismantling, conveying or other incidental expenses can be allowed.

3. The material can be inspected on any working date obtaining the permission of the undersigned.

4. The tenders should be enclosed in sealed cover and delivered at the office on or before the time stipulated above.

5. Each tender must be accompanied by an earnest deposit of Rs. 50. The deposit of unsuccessful tenderers will be returned immediately after one of the tenders is accepted.

6. The final acceptance or rejection of the tender will rest with the Chief Engineer of Mysore, who has discretion to accept any tender or reject all offers without assigning any reason.

7. After one of the tenders is accepted, the fact thereof will be intimated to the successful tenderer who will be allowed a maximum time of 15 days to dismantle and remove the materials and the whole contracted amount should be paid in advance before any material can be allowed to be removed, failing which the contract will be cancelled and the earnest money forfeited.

8. In case of any disputes as regards the weights of materials or other reasons, the decision of the Chief Engineer will be final.

N. LAKSHMINARASIMHAIA,  
Executive Engineer.

#### MYSORE DIVISION

*Notification dated 11th May 1933.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 12 noon on 5th June 1933, for restoring Achammanahalli tank, Krishnarajpete Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Restoring Achammanahalli tank, Krishnarajpete Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for restoring Achammanahalli tank, Krishnarajpete Taluk.

| No. | Items of work                                                                      | Unit  | Quantity |
|-----|------------------------------------------------------------------------------------|-------|----------|
|     | <i>Bund R. L. 55'00.</i>                                                           |       |          |
| 1   | Clearing jungle ...                                                                | Grade | 16       |
| 2   | Cutting grips in old bund ...                                                      | "     | 16       |
| 3   | Earth work excavating for foundation of revetment and using the same for the bund. | Cyds. | 393      |
| 4   | Gravel backing to revetment including carting and consolidating, etc.              | "     | 422      |
| 5   | Earth work to bund including watering and tamping with lead and extra ramps.       | "     | 428      |
| 6   | New stone revetment ...                                                            | "     | 601      |
| 7   | Removing and resetting old stones with new jelly backing.                          | "     | 366      |
| 8   | Turfing to bund slope ...                                                          | Sqr.  | 254      |
| 9   | Preparing and fixing grade stones with cutting figures and painting.               | Each  | 16       |
| 10  | Preparing and fixing Index stones ...                                              |       | 16       |